PROPOSED BURGER KING RESTAURANT

106 and 110 River Road Lisbon, Connecticut Special Permit Application May 3, 2021



Property Location

DEVELOPMENT TEAM

Property Owner

Applicant

Civil and Traffic Engineer

Landscape Architect

Surveyor

River Road Investment Property LLC

New King Inc.

F. A. Hesketh & Associates, Inc.

F. A. Hesketh & Associates, Inc.

F. A. Hesketh & Associates, Inc.

LIST OF DRAWINGS

MA-1

LA-1

LS-1 and LS-2

GR-1 and GR-2

UT-1 SL2

SD-1 thru SD-6

NT-1

Architectural Plan

PTS-1

Title Sheet

Master Plan

Layout Plan

Landscape Plans

Grading, Drainage and SE & SC Plan

Utility Plan

Site Lighting and Photometric Plan

Site Details

Notes

A-1.1 and A-2.1


Property Survey




David S. Ziaks

P.E. #13336

F. A. Hesketh & Assacrate Street Str





SIGNAGE AND PAVEMENT MARKING NOTES

- 1. Stop bars (SB) shall be painted with white traffic paint (12 inches wide)
- All standard parking stalls and centerlines shall be painted with white traffic paint (4 inches wide).
- 3. Traffic control arrows shall be painted with white traffic paint.
- All accessible parking stalls, aisles and symbols of accessibility shall be painted with blue traffic paint (4 inches wide).
- Centerlines shall be painted with yellow traffic paint and shall consist of double lines (4 inches wide)
- Fire lanes and other areas of parking prohibition shall be painted with yellow traffic paint (4 inches wide)
- 7. All on-site traffic paint shall conform to CT DOT Form 818, Article M.07
- All pavement markings and signs shall conform to "Manual On Uniform Traffic Control Devices", "Standard Alphabets For Highway Signs And Pavement Markings", CT DOT 818, State Building Code and ADA Requirements and as shown on the details
- Sign catalog numbers obtained from "Connecticut Department of Transportation, Catalog of Signs", Last Revised 7/3/19. Contractor to confirm sign types prior to installation.
- Install additional fire lane markings and signage as directed by the Lisbon Fire Department Officials.

PAVEMENT MARKING LEGEND

 Symbol
 Type

 SWL
 Painted Single White Line

 SBL
 Painted Single Blue Line

 SYL
 Painted Single Yellow Line

 SB
 Painted White Stop Bar


 DYL
 Double Yellow Centerline


 PCW
 Painted Crosswalk (white paint)

CURB TYPE LEGEND

Symbol

ECC Extruded Concrete Curb






Deciduous	Canopy Trees					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
AFA	Acer x freemanii 'Autumn Blaze'	Autumn Blaze Maple	6	2 to 2 ½ inch caliper	Balled and Burlapped	50 Feet
AXA	Acer x freemanii 'Armstrong'	Armstrong Maple	4	2 to 2 ½ inch caliper	Balled and Burlapped	50 Feet
GTS	Gleditsia triacanthos 'Shademaster'	Shademaster Honeylocust	5	2 to 2 ½ inch caliper	Balled and Burlapped	40 Feet
UAP	Ulmus americana 'Princeton'	Princeton American Elm	2	2 to 2 ½ inch caliper	Balled and Burlapped	70 Feet
UAV	Ulmus americana 'Valley Forge'	Valley Forge American Elm	4	2 to 2 ½ inch caliper	Balled and Burlapped	70 Feet
Deciduous	Flowering Trees					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
PCC	Pyrus calleryana 'Chanticleer'	Chanticleer Flowering Pear	9	1 3 to 2 inch caliper	Balled and Burlapped	40 Feet
Evergreen	Trees					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
TOS	Thuja occidentalis 'Smaragd'	Emerald Green Arborvitae	13	5 to 6 foot height	Balled and Burlapped	15 Feet
Deciduous	Shrubs					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
CR	Cornus racemosa	Gray Dogwood	12	18 to 24 inch height	#3 Container	10 Feet
HMN	Hydrangea macrophylla 'Nikko Blue'	Nikko Blue Hydrangea	7	18 to 24 inch height	#3 Container	4 Feet
MP	Myrica pensylvanica	Northern Bayberry	12	18 to 24 inch height	#3 Container	6 Feet
POS	Physocarpus opulifolius 'Summerwine'	Summerwine Ninebark	13	18 to 24 inch height	#3 Container	4 Feet
RA	Rhus aromatica	Fragrant Sumac	12	18 to 24 inch height	#3 Container	5 Feet
Evergreen	Shrubs					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
JCC	Juniperus chiin. 'Pfitzeriana Compacta'	Compact Pfitzer Juniper	17	18 to 24 inch spread	#3 Container	3 Feet
JCL	Juniperus chinensis 'Gold Lace'	Gold Lace Juniper	9	18 to 24 inch spread	#3 Container	4 Feet
JPK	Juniperus x pfitzer. 'Kallay's Compact'	Kallay's Compact Juniper	25	18 to 24 inch spread	#3 Container	3 Feet
JPS	Juniperus x plitzeriana 'Seagreen'	Seagreen Juniper	9	18 to 24 inch spread	#3 Container	5 Feet
TCC	Taxus cuspidala 'Capitala'	Upright Yew	5	4 to 5 foot height	Balled and Burlapped	Maintain at 6 Feet
Perennials	and Groundcover					
Symbol	Botanical Name	Common Name	Quantity	Size	Root	Mature Height
Symbol					-	

LANDSCAPE NOTES

- 1. All plants shall meet or exceed the specifications of Federal, State and County laws requiring inspection for plant disease and insect control
- Hyde Bailey Hortorium, Cornell University. One plant from each species shall be tagged with name and size of the plant in accordance with the standards of practice of the American Association of Nurserymen. Botanical names shall take precedence over common names
- 4. Plant material shall be typical of their species and/or variety, with a normal habit of growth, sound, healthy and vigorous. They shall be well branched and densely foliated when in leaf, free of disease, insect pest, eggs or lavae. They shall have healthy well-developed root systems. All trees shall have straight single trunks with their main leader intact unless otherwise noted or approved.
- 5. All landscaped areas to have 2" shredded bark mulch (color: black) over weed control fabric. No weed control fabric in areas of groundcover or
- vide protective covering of plant material during delivery and storage. Root balls shall not be cracked or broken. Do not prune plants prior to delivery, ve unacceptable plant material immediately from the job site.
- 7. Plant locations on the Drawings are approximate and are to be used only as a guide. Contractor shall provide all field engineering services to accurately stake out locations for all plants prior to installation. Do not begin excavation until Project Landscape Architect has approved specific layout.
- 8. If requested by Project Landscape Architect, stake and guy each tree as shown on the applicable Drawings immediately after planting. Keep trees plumb and
- 9. If requested by Project Landscape Architect, wrap the trunks of all trees spirally from the ground line to above the lowest main branch
- 10. Perform all cultural care necessary to properly maintain plant viability and keep planted areas in a neat and orderly condition, including but not limited to Watering
 Weed removal
 Apply lime or sulphur to adjust soil pH to specific plant requirements
 Restore or reshape earth saucers

- Adjust and tighten tree supports to maintain plants at their proper grades and vertical position
 Replace mulch to maintain proper depth
- 11. If there is a difference between the quantity of plant material specified on the Plan and the amount depicted on the Landscape Schedule, the amount on the Plan shall take precedence.
- 12. All landscape and lawns areas to have an automatic, mechanical irrigation system



EVERGREEN B&B TREE PLANTING DETAIL

ASSOCIATES, I st Granby, CT 06026
D Fax (860) 844-8600

≪ ∰

Hesketh

Ä

ш.

INC. ROAD

W KING -110 RIVER BON, CONNECT

S

S

NEW 106–110


1" TO 2" CALIPER TREES - MODEL #TS24 2 STAPLES WITH UP TO A 16" ROOT BALL


2" TO 4" CALIPER TREES - MODEL #TS36


2 STAPLES WITH A 24" ROOT BALL


4" TO 6" CALIPER TREES - MODEL #TS42 2-3 STAPLES WITH A 30"+ ROOT BALL


6" TO 8" CALIPER TREES - MODEL #TS48 2-3 STAPLES WITH A 36"+ ROOT BALL











PROPERTY LINE READINGS

Arrangement

SINGLE

Label

A2@45

Luminaire Schedule

Symbol Qty

Illuminance


2 @ 90 DEGREES 0.900 RAR2-320L-110-5K7-4W

Fc

Description

0.900 RAR2-320L-110-5K7-4W





0.10 1.1 0.0 N.A.

100.3

N.A.


.55 16


1.1 16

Lum. Watts EPA Mtg Height Pole Type

SES-13-40-1-XX-XX (4")

SES-13-40-1-XX-XX (4")





Mounting Height=16ft (13ft Pole + 3ft Base) Fixtures Are Full Cutoff Tilt=0 Calculation Grids Are At Grade Pole Maximum 20.4 EPA @ 90MPH

4. THIS LAYOUT MAY NOT MERT TITLE 74 OR LOCAL ENERGY REQUIREMENTS, IT THIS LAYOUT NEEDS TO BE COMPAINAT WITH TITLE 75 OR OTHER RESERV REQUIREMENTS, PLEASE COSSULT FACTORY WITE SPECIFIC DETAILS RECARDING PAGLICE REQUIREMENTS BO THAT REVISIONS MAY BE MADE TO THE DEMAINS.




r	1	die		1 14	•	J
2112 6019		 W.	ko:nq	Restive,	11.	6200

DATE 3/15/2021 1" = 20' 0" BV BV


POINT-BY-POINT FOOTCANDLE PLOT FOR: BURGER KING 106-110 RIVER RD LISBON, CT

NOTES:


- 1. USE SEDIMENT LOG BY AMERICAN EXCELSIOR, OR APPROVED EQUAL
- FOR USE IN SWALES, TURN ENDS SLIGHTLY UP-GRADIENT TO DIRECT RUNOFF TOWARD CENTER OF LOG.
- WHEN BACKING SILT FENCE EROSION CONTROL, INSTALL SILT FENCE FIRST, THEN
 PLACE SEDIMENT LOG IMMEDIATELY BEHIND (DOWN GRADIENT OF) SILT FENCE.



SEDIMENT LOG (SL) SECTION




CONSTRUCTION EXIT (CE)



- NOTE: 1. WOOD POSTS SHALL BE HARDWOOD 1 1/2" x 1 1/2" x 48" MIN. STEEL POST SHALL BE A MINIMUM OF 0.5 POUNDS PER LINEAR FOOT X 48".
- 2. JOINTS, WHEN REQUIRED, SHALL BE SPLICED & SECURELY SEALED TOGETHER, AT POST LOCATIONS ONLY, WITH A MINIMUM 6" OVERLAP.

SEDIMENT FENCE EROSION CONTROL (SFEC)

N.T.S.



1. INSTALL AND MAINTAIN IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS

INLET PROTECTION (IP) [SILT SACK INSERT]

Waterway Installation

Type Weight per Carton Staples per Carton

Distributed By

N. T. S.

ANTI-WASH*/GEOJUTE*

Specifications


Results

1. USE ANTI-WASH/GEOJUTE PRODUCT OR APPROVED EQUAL

EROSION CONTROL BLANKET (ECB)

N. T. S.

Property Fabric structure



853-844-

(860) (860)

Phone Fex

<u>2</u>

≪ ™ .

Hesketh


٩.٤ ٩.٥

Щ ₹

S

HAYBALE EROSION CONTROL (HBEC)


N. T. S




- TOP OF CATCH BASIN A MINIMUM OF 1' ABOVE GRADE.


 COVER TOP OF BASIN WITH GEOTEXTILE FABRIC.
 STAKED HAYBALES OR STONE FILTER BERM TO
 SURROUND BASIN.
 CREATE LOW AROUND BASIN TO COLLECT RUNOFF.
 VOLUME OF LOW AREA PROPORTIONAL TO SIZE OF
 AREA DRAINING TO BASIN.


TEMP. SEDIMENT TRAP AT CATCH BASIN





HAYBALE CHECK DAM (HBCD)











Phone (860) 653-8 Fax (860) 844-8 -mail mail-fahesketh

A. Hesketh

П. №

NC. ROAD


NEW KING 106-110 RIVER


4

SD

STORM SEWER MANHOLE

N.T.S.





SECTION A-A


LEGEND


- S_p { MAX. INSIDE PIPE SPAN (NON CIRCULAR SECTIONS) INSIDE PIPE DIAMETER (CIRCULAR SECTION)
- R_p { MAX. INSIDE PIPE RISE (NON CIRCULAR SECTIONS) INSIDE PIPE DIAMETER (CIRCULAR SECTION)
- Lo { LENGTH OF RIPRAP APRON MEASURED FROM THE END OF CULVERT END SECTION OR FACE OF ENDWALL
- d {12" FOR MODIFIED RIPRAP d {18" FOR INTERMEDIATE RIPRAP 36" FOR STANDARD RIPRAP


	X	La	W,	W ₂	RIPRAP
TYPE A RIPRAP APRON	3		3Sp	3Sp+0.7 La	
LOCATION					
W.Q. BASIN DISCHARGE		20'	3.75	20'	MODIFIED


RIPRAP LEVEL SPREADER (RRLS)


N.T.S.














(860) 653-(860) 844-Mehesketh

Phone

<u>1</u>

& Associates, I East Granby, CT 06026

Hesketh

A.S.

ய

NC. ROAD TICUT

9

SD

SITE DETAILS

PREPARED TOR

NEW KING I

106-110 RIVER F

LISBON, CONNECTI

PROJECT DESCRIPTION:

The proposed project consists of the demolition of existing structures and the construction of a new 2,877 of Burger King Restaurant with a drive-thru along with 44 on-site parking spaces for employees and customers.

Surface drainage will be collected in a conventional storm sewer system comprised of catch basins and manholes, discharging to a detention/water quality basin, which will then discharge to the wetlands and watercourse located on the rear of the property. The project site will be serviced by public water and sanitary sewage along with electric and telephone. The existing town sanitary pump station located on the property will not be impacted by the proposed project.

The approximate date for start of construction is the Summer of 2021. The estimated completion date is spring of 2022.

CONSTRUCTION SEQUENCE:

- In general, the overall project will follow the sequence below:
- Contact "call before you dig" at 1-800-922-4455 at least 48 hours prior to the start of construction to have existing utilities marked.
- Attend a pre-construction meeting with the Owner, Project Engineer, and municipal officials.
- Install construction exit, sediment fence and other SE&SC measures, shown on the Soil Erosion & Sediment Control Plan, as appropriate.
- 4. Stake clearing limits and complete site clearing.
- Strip topsoil in balance of site except in a area where natural vegetation is to remain. Stockpile and stabilize topsoil stockpiles with perimeter silt fencing and temporary seeding. Remove excess topsoil from site.
- Rough grade/fill balance of site. Excavate detention/water quality basin for use as a sediment trap.
- Install storm drainage systems. Install inlet protection in drainage inlet structures.
- Construct building foundations and start building construction.
 Install underground utilities and site lighting.
- Construct gravel subbase and processed aggregate base course for drives and parking areas.
- 11. Install concrete pads, curbs, sidewalks and ramps.
- 12. Install miscellaneous site items.
- 13. Install pavement binder course.
- 14. Place topsoil and establish lawns and install landscaping for balance of project.
- 15. Install pavement wearing course and apply pavement markings and install signs.
- 16. Remove erosion controls after disturbed areas are landscaped and mulched or new lawn areas are stabilized. Complete final cleaning of storm sewer system.

GENERAL NOTES:

- Survey information is taken from a plan entitled "Property Topographic Survey"
 Prepared for River Road Investment Property, LLC, 106 and 110 River Road, Lisbon,
 Connecticut, dated 02-28-2020, revised 02-22-2021 prepared by F. A. Hesketh &
 Assoc., Inc., 1"=40".
- All work and materials to conform to municipal standards, Connecticut D.O.T. Form 818, custodial utility company standards and specifications, or the details shown or these plans, as applicable.
- All work on this project shall be completed in conformance with the requirements of the various federal, State, and local permits issued for this project.
- An Encroachment Permit is required from the CT DOT prior to undertaking any work within the highway ROW. The Contractor is responsible for applying for and obtaining said permit.
- All work on this project shall be completed in conformance with the requirements of the special permit issued for this project.
- 6. A pre-construction meeting and authorization to proceed will be required prior to start of any construction, including removal of trees or stripping of land. Procedures for such pre-construction meeting and authorization to proceed shall be in accordance with Town and State requirements. The contractor is responsible for arranging this meeting with Town and State officials, as applicable.
- Prior to any excavation the contractor shall verify all underground utilities by calling 1-800-922-4455 at least 48 hours in advance.
- 8. The location of all utilities shown is approximate and is based on available as-built information from utility company records, the property owner, and limited aurvey data. All existing utilities may not be shown. The contractor is responsible for determining the exact location of all utilities on the site prior to the start of a contraction activity and notifying the design site engineer of any adjustments to the plans which are necessary. Test pits will be required at all proposed utility crossings and connection locations in order to determine underground utility locations and to the plans. Test pits shall be completed by the contractor at his expense.
- All utilities to be installed in accordance with governing/custodial utility company
 applicable requirements. Final location of utility connections is subject to revision
 by individual utility companies prior to the installation. The contractor is
 responsible for coordinating the work with the custodial utility companies.
- 10. Erosion and sedimentation control measures shall be installed and maintained in accordance with the plans, specifications, the Soil Erosion and Sedimentation Contro Plan and notes, and in accordance with any Town and State requirements.
- 11. Trees shall be flagged and approved, prior to removal.
- No stumps, logs, brush, construction debris, or deleterious materials are to be buried on site.
- 13. The contractor shall maintain the site in a neat and orderly manner throughout the construction period. All debris shall be removed from the site by the contractor, and properly disposed, off site, in accordance with applicable laws.
- 14. Utility service shall be maintained at all times.
- Drainage shall be maintained throughout the project so as not to cause flooding of roadways or damage to private property.
- 16. All new site utilities are to be installed underground.
- Trees and vegetation identified to be saved shall be protected from construction equipment by suitable means approved by Town staff.
- 18. All exterior lighting shall not be directed onto abutting properties or roadways.
- Removal of trees or other vegetation, or re-grading substantially different from that shown on the approved site plan, will not be permitted without prior authorization by the Town or State, as applicable.
- All construction vehicles, equipment and materials are to enter the site via the construction entrance/exit directly to River Road.
- 21. All approvals, as required by the State of Connecticut DOT, shall be part of the conditions of approval.
- Any additional revisions to the plans shall be submitted to the Town Engineer and the Planning Department for review and approval prior to the issuance of a building permit.

EROSION AND SEDIMENT CONTROL NOTES

- Disturbance of soil surfaces is regulated by State Law. All work shall comply with an
 approved "Soil Erosion and Sediment Control Plan" to prevent or minimize soil erosion
- 2. The installation and maintenance of erosion control devices is the responsibility of the land owner, developer, and the excavation contractor. Town officials shall be notified in writing of the name, address and telephone number of the individual responsible for this work (including any changes) at the required pre-construction conference.
- The contractor shall use the "Connecticut Guidelines For Soil Erosion And Sediment Control" (2002), as amended as a guide in construction the erosion and sediment controls indicated of the plans. The guidelines may be obtained from the Connectic DEEP, 79 Elm Street, Hartford, CT, 06106-5127.
- The contractor shall schedule operations to limit disturbance to the smallest practical area for the shortest possible time. Overall site disturbance shall be confined to those limits delineated on the plans.
- The contractor is responsible for the timely installation, inspection, repair or replacement of erosion control devices to insure proper operation.
- The contractor shall notify the design engineer of unsatisfactory erosion conditions not controlled by the Soil Erosion and Sediment Control Plan and shall install additional measures as required.
- All disturbed areas not covered by buildings, pavement, mulch or ground cover plantings shall be planted with grass.
- Accumulated sediment removed from erosion control devices is to be spread and stabilized in level, erosion resistant locations as general fill.
- Special attention shall be given to the construction sequence outlined on Grading and Erosion Control Plan.
- 10. The developer shall be responsible for cleaning any construction debris or sediment from existing roads as ordered by the Town and/or State, if any debris or sediment from construction activities enter onto these roadways.
- Limit work within wetland areas to the least disturbance necessary for construction Restore disturbed areas as closely as possible to their original natural state.
- Additional dust control measures as specified in D.O.T. 818 Section 9.39, Section 9.42
 and Section 9.43 shall be furnished by the contractor as site conditions warrant or as
 directed by Town or State officials.
- 13. The contractor is responsible for cleaning and removal of sediment and/or debris from the storm drainage system throughout the duration of the project (i.e. silt sacks, sumps, etc.)
- 14. A pre-construction meeting is recommended with the Town of Lisbon and/or Consultant(s) prior to the start of construction to inspect E & S control measures and to discuss construction sequencing/phasing.
- 15. The Owner/Developer shall add erosion and sedimentation control measures as deemed necessary by the Town of Lisbon staff and/or Consultant(s) throughout the construction process.

EROSION CONTROL DEVICES:

Refer to the "Connecticut Guidelines For Soil Erosion And Sediment Control - 2002" (see Erosion and Sediment Control Note 3) when constructing erosion control devices shown on this plan.

HBEC - HAYBALE EROSION CHECKS shall be staked a minimum of five (5) feet from the base of disturbed slopes exceeding eight (8) feet in height, or at locations shown on the plans. Place haybales before starting a fill slope and after digging a cut slope. Heel haybales 4' into the soil. Stake haybales around the perimeter of all catch basins. Remove all sediment when deposits reach 1/2 bale height. Haybales must be replaced periodically.

SFEC - SEDIMENT FENCE EROSION CHECK: a synthetic textile barrier designed to filter sediment from surface water runoff. Placement shall be similar to HBEC and installation requires anchoring the fence bottom to prevent bypass. All sediment shall be removed if deposits reach one (1) foot in depth. Additional support (such as snow fence or wire fence) on the downhill face may be required to strengthen sediment fence in high flow locations.

CE - CONSTRUCTION EXIT: a broken stone pad providing a hard surface points where vehicles will leave the site. The construction exits reduce tracking of sediment into adjacent pavement. Excess sediment should be periodically removed from the stone surface.

GRSW - GRASSED SWALE: a shaped shallow earth drainage way used to convey excess surface runoff. Grass vegetation should be well established before use. Stabilization with neiting or mulch may be required.

IP — INLET PROTECTION: a sediment control device used during construction that mounts under the grate of a catch basin, residing inside the structure. It is made of permeable geotextile that allows water to pass, but traps stilt and sediment. (Silt Sack or approved equal.) The silt sack must be removed when silt/sediment reaches one half the height of the device. Removes sediments and deposit on stable area of site and rinse devise for reuse. Replace when damaged.

SL - SEDIMENT LOGS: A sediment control device consisting of an outside, open weave containment fabric filled with fibers. It is designed to provide a flexible, lightweight, porous, sediment control device with the ability to conform to the terrain upon which it is installed. It is designed to dissipate velocity of flow and filter and trap sediments upgraddent and within the device.

RRPP - RIP RAP PLUNGE POOL: A riprap lined apron installed at a zero percent grade to absorb the initial impact of stormwater discharge from the storm drainage system and further reduce flow velocities to prevent erosion downstream. RRPP is designed per the "Connecticut Department of Transportation, Drainage Manual - 2000"

ECB - EROSION CONTROL BLANKET: A manufactured blanket composed of biodegradable/photodegradable natural or polymer fibers and/or filaments that have been mechanically, structurally or chemically bound together to form a continuous matrix.

(860) (860) Phone Fax <u>2</u> Associates, at Granby, CT 06026 **∞** ∰ ≀ Hesketh A.S. Щ. § h INC. ROAD TICUT

3 4

N-T

