SITE DEVELOPMENT PLAN

PREPARED FOR

SUNFOX CAMPGROUND, LLC

15 KENYON ROAD LISBON, CONNECTICUT NOVEMBER 20, 2020 REVISED DECEMBER 7, 2021

CIVIL DRAV	VING INDEX
SHEET NUMBER	SHEET TITLE
1	COVER SHEET
2	EXISTING CONDITIONS 1 OF 2
3	EXISTING CONDITIONS 2 OF 2
4	SITE PLAN
5	SITE PLAN
6	SITE PLAN
7	SITE PLAN
8	CONSTRUCTION DETAILS
9	CONSTRUCTION DETAILS
10	EROSION AND SEDIMENTATION CONTROL DETAILS
11	EROSION AND SEDIMENTATION CONTROL NARRATIVE & NOTES
12	IMPACT ESTIMATES

PROPERTY OWNER: SUNFOX CAMPGROUND, LLC 15 KENYON ROAD

LISBON, CONNECTICUT 06351

APPLICANT: SUNFOX CAMPGROUND, LLC

15 KENYON ROAD LISBON, CONNECTICUT 0635

ZONING DISTRICT: R-60

EXISTING USE: CAMPGROUND


PROPOSED USES: CAMPGROUND





PROPERTIES	WITHIN 500'
ADDRESS	OWNER
0 KENYON RD	JEWETT CITY WATER COMPANY
3 KENYON ROAD	WELDON E FRENCH
5 KENYON ROAD	SUNFOX CAMPGROUND LLC
9 KENYON ROAD	HECTOR N MARIEN
10 KENYON RD	PETER G PISOWLOSKI
13 KENYON RD	CHRISTINE BRANCO HEALY
19 KENYON ROAD	JEFFREY T RECK
20 KENYON ROAD	JOHN PAUL & DAWN COUGHLIN
22 KENYON ROAD	SUNFOX CAMPGROUND LLC
23 KENYON ROAD	ROBERT RICHMAN
20 STRNAD ROAD	JEFFREY T BUCKRIDGE
21 STRNAD ROAD	DAVID L SCOTT
24 STRNAD ROAD	MICHAEL P THOMAS
25 STRNAD ROAD	PAMELA COTE
26 STRNAD ROAD	MICHAEL F HYDE
27 STRNAD ROAD	DANIELLE BERRIOS
29 STRNAD ROAD	MAHLON D CURRIER Jr.
30 STRNAD ROAD	AMANDA CARON
31 STRNAD ROAD	TIMOTHY R PHILBRICK
32 STRNAD ROAD	KENNETH A LU WOHLLEBEN, BRIAN K WOHLLEBEN, & WENDY A SNAY
33 STRNAD ROAD	DAWN A COMBIES
117 SOUTH BURNHAM HIGHWAY	STILLY'S HOLDINGS LLC
125 SOUTH BURNHAM HIGHWAY	ENRICO & SUSAN COVINO
129 SOUTH BURNHAM HIGHWAY	ENRICO & SUSAN S COVINO
143 SOUTH BURNHAM HIGHWAY	PERFECT PROPERTY LLC
174 SOUTH BURNHAM HIGHWAY	RICHARD M CZIKOWSKY
215 SOUTH BURNHAM HIGHWAY	RICHARD ALLEN STRNAD
29 KENDALL ROAD	WILLIAM C SURFUS
37 KENDALL ROAD	DONNA M & STEPHEN E JOHN
49 KENDALL ROAD	SALLY A KNOLHOFF
55 KENDALL ROAD	ROBERT L LACHAPELLE
77 KENDALL ROAD	SUNFOX CAMPGROUND LLC
78 KENDALL ROAD	TOWN OF LISBON
72 PRESTON ALLEN ROAD	MACY L MERRY & CAITLIN E MONTELLA
84 PRESTON ALLEN ROAD	ROBERT T BROWN
86 PRESTON ALLEN ROAD	MICHALE W ROLFE
90 PRESTON ALLEN ROAD	CHRISTINE KNOGHT
94 PRESTON ALLEN ROAD	SHARON K LU GLEASON
128 PRESTON ALLEN ROAD	SANDRA L EDMOND
144 PRESTON ALLEN ROAD	GARY MOLOCHKO
23 MELL ROAD	JOHN F ALGIERE





APPROVED BY THE LISBO PLANNING & ZONING COMMI	
APPLICATION:	
APPROVED ON:	
CHAIRMAN OR SECRETARY SIGNATURE	DATE
























NOT TO SCALE

MAXIMUM SHEETING AS MÁTÉRIÁL ÓR / BORRÓW / DIAMETER TRENCH WIDTH REQUIRED (TYPICAL) ----PROVIDE TRACER TAPE --- COMPACTED SAND CUSHION * FILTER FABRIC ✓— 3/4" CRUSHED STONE BEDDING MATERIAL * 1/4 OD 6" MIN. - 12" FOUNDATION STONE WHEN st12" MINIMUM IN UNSUITABLE MATERIAL OR ORGANIC ROCK EXCAVATION -SILT IS ENCOUNTERED AT SUBGRADE TRENCH BOTTOM —

TRENCH SECTION FOR SANITARY SEWER & STORM DRAINS NOT TO SCALE


NOTE:
BACKFILL MATERIAL TO BE PLACED IN 12" MAXIMUM LIFTS
& COMPACTED TO 95% MAXIMUM DRY DENSITY
(AS DETERMINED BY THE MODIFIED PROCTOR METHOD)

* PROVIDE NATIVE MATERIAL WITHIN 50' OF SEPTIC SYSTEM LEACHING FIELDS





TRENCH SECTION FOR TYPICAL WATER TRENCH NOT TO SCALE

BACKFILL MATERIAL TO BE PLACED IN 12" MAXIMUM LIFTS & COMPACTED TO 95% MAXIMUM DRY DENSITY (AS DETERMINED BY THE MODIFIED PROCTOR METHOD)




BURIED CABLE TRENCH
CROSS SECTION
NOT TO SCALE






CAMP SITE SANITARY SERVICE STAND PIPE DETAIL




CAMP SITE WATER SERVICE STAND PIPE DETAIL

NOT TO SCALE

SITE DEVELOPMENT PLAN	PREPARED FOR	DAVID NOWAKOWSKI	15 KFNYON ROAD	LISBON, CONNECTICUT		CONSTRUCTION DETAILS	
	BY	RAC	РМР	RAC	РМР		
REVISIONS	DESCRIPTION	02/10/2021 HEALTH COMMENTS	04/02/2021 CT DPH COMMENTS	3 06/15/2021 CT DPH COMMENTS			
RE	DATE	02/10/2021	04/02/2021	06/15/2021	12/07/2021 PZC COMMENTS		
	ON	-	2	3	4		
JOB DATA	PROJECT 2019160	BOOK NO. 192	DESIGNED KLD/PMP	DRAWN ZBC/RAC	СНЕСКЕD КLD	COGO FILE 2019160 ALL	FILE 2019160 STP.dwg
	ATE			/20			
(LE:					
))/ `	.ı⊢(`		#ZU	191	υøι	



STANDARD SANITARY MANHOLE DETAIL NOT TO SCALE



FRAME AND COVER NOT TO SCALE


SEPTIC SYSTEM FILL MATERIAL SPECIFICATIONS

1.) THE FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THREE(3) INCHES. 2.) UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SIEVE (THIS IS THE GRAVEL PORTION OF THE SAMPLE). 3.) THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE


ANALYSIS STARTED 4.) THE REMAINING SAMPLE SHALL MEET THE FOLLOWING GRADATION CRITERIA. PERCENT PASSING

	I LIVOLIVI	1 7331110
SIEVE SIZE	WET SIEVE	DRY SIEVE
#4	100%	100%
#10	70%-100%	70%-100%
#40	10%-50% *	10%-75%
#100	0%-20%	0%-5%
#200	0%-5%	0%-2.5%

*NOTE: PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10% AND THE #200 DOES NOT EXCEED 5%




CAPACITIES A B C W L 2500 GAL 77" 60" 57" 7' 15'



2 COMPARTMENT H20 RATED SEPTIC TANK


NOTE: PROVIDE INLET BAFFLE & OUTLET FILTER AS REQUIRED BY HEALTH CODE




STANDARD CLEAN-OUT DETAIL

BOTTOM = 144.75 ----


→ 6"






1000 GALLON H-20 RATED PUMP CHAMBER NOT TO SCALE

PROVIDE GALVANIZED RAIL SYSTEM






END VIEW 18" HIGH FLOW DIFFUSOR NOT TO SCALE

DESIGN NOTES


1) EIGHT OUTLETS AND THREE INLETS 2) INLET AND OUTLETS HAVE STATE APPROVED SEALS THAT ACCEPT 4" S-40, 4" SDR-35, 3" AND 2" PIPE. 3) REINFORCED WITH #3 BARS 4) CONCRETE STRENGTH 4000 PSI MIN. 28 DAYS




DISTRIBUTION BOX /W BAFFLE NOT TO SCALE

JOLLEY PRECAST 1,000 GALLON H20 LOADING SINGLE COMPARTMENT SEPTIC TANK INSIDE DIMENSIONS OF CHAMBER = 4.625' WIDE X 7.5' LONG X 4.5' HIGH

DUPLEX PUMPS SHALL BE MYERS CONTINUOUS DUTY STAINLESS STEEL PUMP MODEL DE40PC1 2" DISCHARGE ALTERNATING SYSTEM OR EQUAL AS APPROVED BY THE ENGINEER. DISCHARGE LINE SHALL BE INSTALLED WITH 4' OF COVER TO PREVENT FREEZING. ALARM SHALL BE LOCATED IN THE PAVILION BUILDING AND BE POWERED BY A CIRCUIT SEPARATE FROM THE CIRCUIT OF THE PUMP. THE ALARM SHALL BE LOCATED IN AN AREA WHERE IT WILL BE EASILY AUDIBLE. ELECTRICAL CONNECTIONS SHALL BE MADE IN CODE COMPLIANT ACCESS BOXES OUTSIDE OF THE PUMP CHAMBER. PUMP DISCHARGE LINE SHALL BE FITTED WITH UNION TO ALLOW EASY REMOVAL OF THE





STANDARD D-BOX NOT TO SCALE

CONSTRUCTION SCHEDULE

1.) REMOVE AND STOCKPILE TOPSOIL.
2.) PLACE SELECT FILL ACCORDING TO CT. STATE HEALTH CODE REQUIREMENTS.
3.) EXCAVATE 4' WIDE TRENCHES AND PREPARE SURFACE.
4.) FILL TRENCHES WITH APPROVED AGGREGATE TO HEIGHT OF PIPE INVERTS PLACE PIPE IN TRENCH, AND FILL TO 2" OVER TOP OF PIPE. 5.) CAP ENDS OF PIPES. 6.) PLACE A 4' WIDE STRIP OF NON-WOVEN FILTER FABRIC ON TOP OF THE ENTIRE LENGTH OF THE SYSTEM, AND BACKFILL WITH NATIVE MATERIAL.
7.) REPLACE TOPSOIL, SEED & MULCH.

CONSTRUCTION NOTES

1.) BOTTOM OF ALL TRENCHES AND LEACHING PIPE SHALL BE LEVEL THROUGHOUT UNDER NO CIRCUMSTANCES SHALL ANY PIPE IN A TRENCH HAVE A PITCH EXCEEDING 1" 2.) PIPE BETWEEN THE HOUSE AND THE SEPTIC TANK SHALL BE SCHED. 40 ASTM D
1785 PVC:THIS PIPE SHALL HAVE A MINIMUM SLOPE OF 0.25" PER 1'.
3.) ALL DISTRIBUTION PIPES TO BE 4" PVC OR POLYETHYLENE PIPE AS SPECIFIED IN
SEC. 19-13-B103, TABLE 5 OF THE CT. STATE HEALTH CODE.
4.) ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH CT. STATE HEALTH CODE. 5.) ALL TOPSOIL IN THE LOCATION OF THE PROPOSED SYSTEM SHALL BE REMOVED AND STOCKPILED PRIOR TO EXCAVATION.

6.) FILL MATERIAL FOR SEPTIC AREA IS TO BE SELECT FILL PER CT. STATE HEALTH CODE 7.) SEPTIC TANKS AND DISTRIBUTION BOXES SHALL BE PLACED ON 6" COMPACTED 8.) RESERVE LEACHING AREA TO BE OF EQUAL SIZE TO PRIMARY LEACHING AREA.

O P	B DATA		RE	REVISIONS		
PROJECT	2019160	Ö	DATE	DESCRIPTION	BY	
BOOK NO.	192	-	02/10/2021	02/10/2021 HEALTH COMMENTS	RAC	
DESIGNED	KLD/PMP	7	04/02/2021	04/02/2021 CT DPH COMMENTS	РМР	
DRAWN	ZBC/RAC	М	06/15/2021	06/15/2021 CT DPH COMMENTS	RAC	
CHECKED	KLD	4	12/07/2021	12/07/2021 PZC COMMENTS	РМР	
COGO FILE	COGO FILE 2019160 ALL					
FILE	2019160 STP.dwg					

OWAKOWSKI

AVID

TION


TRUC


CONS

DATE: 11/20/2020 SCALE: 1" = 40

PROJECT: #2019160

SHEET 9 OF 12






- 1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12"
- 3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SÒIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. (STAPLE PATTERN DEPICTED IS SCHEMATIC ONLY. SEE MANUFACTURER'S LITERATURE FOR REQUIRED STAPLE PATTERNS)
- 4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" OVERLAP DEPENDING ON BLANKET TYPE.
- 5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET

CRITICAL POINTS A. OVERLAPS & SEAMS B. PROJECTED WATER LINE C. CHANNEL BOTTOM/SIDE SLOPE VERTICES

- 1. HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITICAL POINTS ALONG THE CHANNEL SURFACE.
- 2. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENTHS IN EXCESS OF 6" (15 CM) MAY BE NECESSARY TO PROPERLY ANCHOR THE BLANKETS.

EROSION CONTROL BLANKET NTS

SILT FENCE



WOVEN WIRE FENCE (MIN. 14 1/2 GAUGE W/ MAX. 6" MESH — SPACING) WITH FILTER CLOTH 36" MIN. FENCE POST -UNDISTURBED GROUND COMPACTED SOIL EMBED FILTER CLOTH A MIN. OF 6" IN GROUND

SECTION VIEW

CONSTRUCTION SPECIFICATIONS


1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES, POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD.


2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION, FENCE SHALL BE WOVEN WIRE, 6" MAXIMUM MESH OPENING.

3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED, FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILNKA T140N, OR APPROVED


4. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT.

5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.





WOOD CHIP BERM DETAIL



STAKE ——

PLACEMENT OF A STRAW BALE BARRIER

SION 0 DATE: 11/20/2020

SCALE: 1" = 20'

PROJECT: #2019160

SHEET

10 OF 12

EROSION AND SEDIMENTATION CONTROL NARRATIVE & NOTES

PROJECT NARRATIVE

THIS PROJECT CONSISTS OF THE CONSTRUCTION OF THIRTY TWO CAMP SITES WITH ASSOCIATED UTILITIES AND ACCESS ROAD IN LISBON, CONNECTICUT.

THIS PROJECT REQUIRES THE FOLLOWING PERMITS: UNCAS HEALTH DISTRICT SSDS

THIS PROJECT REQUIRES THE APPROVAL OF THE FOLLOWING BOARDS/COMMISSIONS:

TOWN OF LISBON CONSERVATION COMMISSION (APPLICATION #21-005 APPROVED ON 8/17/2021)

TOWN OF LISBON PLANNING AND ZONING COMMISSION

ESTIMATED CONSTRUCTION SCHEDULE

- A. INSTALL EROSION AND SEDIMENT CONTROL SYSTEMS OCTOBER 2021
- B. ROUGH GRADE SITE OCTOBER DECEMBER 2021
- C. INSTALL UTILITIES AND SEPTIC SYSTEMS MARCH JUNE 2021
- D. CONSTRUCT ROADWAY JULY 2022
- F. FINISH GRADE SITE AUGUST OCTOBER 2022

PROJECT SEQUENCE

- A. STAKEOUT LIMIT OF DISTURBANCE.
- B. HOLD PRECONSTRUCTION MEETING.
- C. CONTACT "CALL BEFORE YOU DIG" AT 1-800-922-4455 (CT) OR CONTACT "DIG SAFE" AT 1-888-344-7233. (MA) TWO (2) WORKING DAYS PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY.
- D. INSTALL CONSTRUCTION ENTRANCE.
- E. INSTALL TOE OF SLOPE PERIMETER FILTER (SILT FENCE OR HAYBALES) DOWN GRADIENT FROM ALL AREAS OF LAND CLEARING AND CONSTRUCTION ACTIVITY.
- F. PERFORM ALL NECESSARY CLEARING AND GRUBBING OPERATIONS.
- G. EXCAVATE ALL STUMPS LOCATED AND REMOVE TO A STOCKPILE AREA TO BE
- H. STRIP AND STOCKPILE TOPSOIL IN AN APPROVED AREA AND SECURE WITH EROSION AND SEDIMENT CONTROLS.
- I. ROUGH GRADE PROPOSED ROADWAY.
- J. CONSTRUCT SEPTIC SYSTEM.
- K. GRADE CAMP SITES.
- L. INSTALL UTILITIES
- M. INSTALL AND GRADE ROADWAY SUBBASE.
- N. INSTALL PROCESSED AGGREGATE IN CAMP SITES
- O. FINISH GRADE ROADWAY.
- P. COMPLETE THE BALANCE OF SITE WORK AND STABILIZATION OF ALL OTHER DISTURBED AREAS.
- P. REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS.

NOTES:

- SEVERAL OF THE ABOVE ACTIVITIES MAY BE DONE SIMULTANEOUSLY.
- THE DEVELOPMENT IS EXPECTED TO PROCEED WITH STABILIZATION OCCURRING AS GRADING PROCEEDS. DISTURBANCE IS NOT EXPECTED TO EXCEED ONE(1) ACRE AT ANY ONE TIME. A SEDIMENT TRAP, PER CT SEDIMENT AND EROSION CONTROL MANUAL, MUST BE INSTALLED IF MORE THAN ONE(1) DISTURBED ACRES WILL DISCHARGE TO ONE AREA.

SEEDING SPECIFICATIONS

- A. IF GROUND HAS BEEN PREVIOUSLY MULCHED, MULCH MUST BE REMOVED OR ADDITIONAL NITROGEN MUST BE ADDED.
- B. REMOVE ALL SURFACE STONES 2" OR LARGER AS WELL AS ALL DEBRIS SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, CLUMPS, OR OTHER UNSUITABLE MATERIAL.
- C. APPLY FERTILIZER AT 7.5 POUNDS PER 1,000 SQUARE FEET AND LIME AT 200 POUNDS PER 1,000 SQUARE FEET UNLESS SOIL TESTING FOR REQUIREMENTS IS PERFORMED.
- D. NO MOWING IS TO BE UNDERTAKEN UNTIL THE MAJORITY OF THE VEGETATION IS AT LEAST 6" HIGH. MOWING SHOULD CUT THE TOP 1/3 OF VEGETATION. DO NOT UNDER ANY CIRCUMSTANCES CUT VEGETATION BELOW 3".
- E. DO NOT APPLY ANY FORM OF WEED CONTROL UNTIL GRASS HAS BEEN MOWED AT LEAST 4 TIMES.
- F. THESE SEEDING MEASURES ARE NOT TO BE USED ON SLOPES IN EXCESS OF 2:1 GRADING.

 C. PERMANENT SEEDING MEASURES ARE TO BE USED INSTEAD OF TEMPORARY
- G. PERMANENT SEEDING MEASURES ARE TO BE USED INSTEAD OF TEMPORARY SEEDING MEASURES WHERE WORK IS TO BE SUSPENDED FOR A PERIOD OF TIME LONGER THAN 1 YEAR.
- H. IF THERE IS NO EROSION, BUT SEED SURVIVAL IS LESS THAN 100 PLANTS PER SQUARE FOOT AFTER 4 WEEKS OF GROWTH, RE—SEED AS PLANTING SEASON ALLOWS.
- I. ALL DISTURBED AREAS OUTSIDE THE PAVEMENT AREA, WITHIN AND OUTSIDE THE ROAD RIGHT OF WAY, SHALL BE RESTORED IN ACCORDANCE WITH THE CITY/TOWN SUBDIVISION REGULATIONS.

EROSION & SEDIMENT CONTROL OPERATIONS AND MAINTENANCE

- A. EROSION AND SEDIMENTATION CONTROL AND RESTORATION MEASURES SHALL CONFORM TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENTATION CONTROL", PUBLISHED BY THE CONNECTICUT COUNCIL OF SOIL AND WATER CONSERVATION AND THE CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION AND TO TOWN REGULATIONS.
- B. INSTALLATION OF SEDIMENT AND EROSION CONTROLS SUCH AS HAYBALES AND SILT FENCES SHALL BE ESTABLISHED PRIOR TO COMMENCING ANY LAND DISTURBANCE ACTIVITIES.
- C. ALL STOCKPILED MATERIAL SHALL BE RINGED WITH HAYBALES OR SILT FENCES.
 ANY MATERIAL TO BE STOCKPILED LONGER THAN 14 DAYS SHALL BE STABILIZED
 WITH TEMPORARY SEEDING OR JUTE NETTING.
- D. HAYBALE FILTERS OR SILT FENCE SHALL BE PLACED 5-10 FEET FROM THE TOE OF ALL CRITICAL SLOPES AS SHOWN ON THE PLAN. THESE SHALL BE CHECKED BY THE CONTRACTOR REGULARLY AND REPAIRED WHENEVER THEY FAIL TO INSURE CLEAN RUN-OFF FROM THE SITE.
- E. ADDITIONAL CONTROL MEASURES IF REQUESTED BY THE TOWN SHALL BE INSTALLED IMMEDIATELY UPON REQUEST.
- F. ALL DISTURBED AREAS SHALL BE PROTECTED WITH A MINIMUM VEGETATION COVER AS SHOWN IN ACCOMPANYING CHART.
- G. THE CONTRACTOR SHALL PLAN ALL LAND DISTURBING ACTIVITIES IN A MANNER AS TO MINIMIZE THE EXTENT OF THE DISTURBED AREAS.
- H. THE CONTRACTOR SHALL MAKE DAILY INSPECTIONS OF THE SITE TO INSURE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES AND WILL IMMEDIATELY MAKE NECESSARY REPAIRS IF REQUIRED BY THE CITY/TOWN.
- I. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSPECTED AT A MINIMUM OF ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL AMOUNT OF 0.1 INCHES OR GREATER TO DETERMINE MAINTENANCE NEEDS.
- J. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REPLACED WITHIN 24 HOURS OF AN OBSERVED FAILURE.
- K. ALL CONSTRUCTION TRAFFIC SHALL ENTER AND LEAVE BY THE DESIGNATED ENTRANCE. THIS ENTRANCE SHALL BE CONSTRUCTED OF CRUSHED STONE TO HELP FREE TIRES OF SOIL WHEN LEAVING THE SITE. THE CONTRACTOR SHALL INSTRUCT ALL VEHICLE DRIVERS TO CLEAN SOIL MATERIAL FROM TIRES IN FRONT OF THE SITE. ALL SOIL, MISCELLANEOUS DEBRIS, OR OTHER MATERIAL SPILLED, DUMPED OR OTHERWISE DEPOSITED ON PUBLIC STREETS, HIGHWAYS, SIDEWALKS OR OTHER PUBLIC THOROUGHFARES DURING TRANSIT TO OR FROM THE SITE SHALL BE REMOVED PROMPTLY.
- O. THE CONTRACTOR HEREBY ACKNOWLEDGES HIS RESPONSIBILITY TO INSTALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES ON THIS SITE AND THAT HIS FAILURE TO INSTALL AND MAINTAIN THESE DEVICES COULD RESULT IN FINES OR SUSPENSION OF WORK BY THE CITY/TOWN.
- P. MINIMIZE OR ELIMINATE ANY UNNECESSARY LAND DISTURBANCE OR CLEARING.

HAYBALE SPECIFICATIONS

- A. ALL HAYBALES SHALL BE EITHER WIRE OR STRING BOUND. HAYBALES SHALL BE INSTALLED SO THAT BINDINGS ARE ORIENTED ALONG THE SIDE RATHER THAN ALONG THE TOP AND BOTTOM OF THE BALES TO PREVENT DETERIORATION OF
- B. GAPS BETWEEN HAYBALES SHALL BE CHINKED WITH STRAW TO PREVENT WATER FROM ESCAPING BETWEEN BALES.
- ON SLOPES WHERE SURFACE FLOW FOLLOWS THE HAYBALE LINE, PERPENDICULAR HAYBALE CHECKS SHALL BE INSTALLED AT 50 FOOT INTERVALS.
- D. HAYBALES SHOULD NEVER BE USED FOR ANY APPLICATION WHERE SEDIMENT AND EROSION PROTECTION IS REQUIRED FOR A PERIOD OF TIME LONGER THAN 3 MONTHS.
- E. HAYBALES SHOULD HAVE A MINIMUM WEIGHT OF 40 POUNDS AND A MAXIMUM WEIGHT OF 120 POUNDS.
- F. LINES OF HAYBALES SHOULD FOLLOW CONTOUR LINES 5—10 FEET DOWN GRADIENT FROM THE SLOPE. WHERE CONTOUR LINES CAN NOT BE FOLLOWED HAYBALES SHOULD BE STAGGERED AND PERPENDICULAR WINGS SHOULD BE PLACED AT 50 FOOT INTERVALS.
- G. HAYBALES SHOULD BE PLACED IN AN EXCAVATED TRENCH AT LEAST 4" DEEP.
- H. HAYBALE STAKES ARE TO BE MADE OUT OF HARDWOOD WITH A MINIMUM CROSS SECTIONAL AREA OF 1.5 SQUARE INCHES OR STEEL POSTS WITH A MINIMUM WEIGHT OF 0.5 POUNDS PER LINEAR FOOT.

SILT FENCE SPECIFICATIONS

3. ELONGATION AT FAILURE

- A. SYNTHETIC FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER, ETHYLENE, OR SIMILAR FILAMENTS AND SHALL BE CERTIFIED BY THE MANUFACTURER OR SUPPLIER AS CONFORMING TO THE FOLLOWING MINIMUM REQUIREMENTS:
 - 1. FILTERING EFFICIENCY 75 PERCENT (MIN)
 2. GRAB TENSILE STRENGTH 100 POUNDS
 - 4. MULLEN BURST STRENGTH 250 POUNDS PER SQUARE INCH
- 5. PUNCTURE STRENGTH 50 POUNDS
- 6. APPARENT OPENING SIZE 0.60mm< X <0.90mm

15 PERCENT

EXPOSURE (MIN)

7. FLOW RATE

0.2 GALLONS PER SQUARE FOOT PER MINUTE

8. PERMITTIVITY

0.05 PER SECOND (MIN)

9. ULTRAVIOLET RADIATION STABILITY 70 PERCENT AFTER 500 HOURS OF

- 3. STAKES ARE TO BE MADE OUT OF HARDWOOD WITH A MINIMUM CROSS SECTIONAL AREA OF 1.5 SQUARE INCHES OR STEEL POSTS WITH A MINIMUM WEIGHT OF 0.5 POUNDS PER LINEAR FOOT.
- C. TORN OR PUNCTURED GEOTEXTILES SHALL NOT BE USED.
- ON SLOPES WHERE SURFACE FLOW FOLLOWS THE SILT FENCE LINE, PERPENDICULAR SILT FENCE CHECKS SHALL BE INSTALLED AT 50 FOOT INTERVALS.
- E. LINES OF SILT FENCE SHOULD FOLLOW CONTOUR LINES 5—10 FEET DOWN GRADIENT FROM THE SLOPE. WHERE CONTOUR LINES CAN NOT BE FOLLOWED PERPENDICULAR WINGS SHOULD BE PLACED AT 50 FOOT INTERVALS.

GENERAL NOTES

- ALL UTILITIES SHALL BE APPROVED BY LOCAL UTILITY COMPANIES PRIOR TO CONSTRUCTION; ALL UTILITIES SHALL BE CONSTRUCTED TO UTILITY COMPANY SPECIFICATIONS
- 2. ALL CONSTRUCTION SHALL BE TO TOWN SPECIFICATIONS & REGULATIONS.
- 3. NO CHANGES CAN BE MADE TO THESE PLANS WITHOUT THE DESIGN ENGINEER'S APPROVAL. FIELD CHANGES SHALL HAVE PRIOR APPROVAL OF THE ENGINEER.
- 4. CONTRACTOR SHALL NOTIFY THE DESIGN ENGINEER OF CONSTRUCTION SCHEDULE SO THAT INSPECTION MAY BE PROVIDED.
- 6. UNDERGROUND UTILITY, STRUCTURE AND FACILITY LOCATIONS DEPICTED ON PLANS HAVE BEEN COMPILED, IN PART, FROM RECORD MAPPING SUPPLIED BY THE RESPECTIVE UTILITY COMPANIES OR GOVERNMENTAL AGENCIES, FROM PAROLE TESTIMONY, FIELD MEASUREMENTS AND FROM OTHER SOURCES. THESE LOCATIONS MUST BE CONSIDERED APPROXIMATE IN NATURE. ADDITIONALLY, OTHER SUCH FEATURES MAY EXIST ON THE SITE, THE EXISTENCE OF WHICH ARE UNKNOWN TO CHA COMPANIES. THE SIZE, LOCATION AND EXISTENCE OF ALL SUCH FEATURES MUST BE FIELD DETERMINED AND VERIFIED BY THE APPROPRIATE AUTHORITIES PRIOR TO CONSTRUCTION.
- 7. CONTACT "CALL BEFORE YOU DIG" AT 811 OR 1-800-922-4455 TWO (2) WORKING DAYS PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY.
- 8. FIRE LANES, IF REQUESTED BY THE FIRE MARSHAL, SHALL BE INSTALLED AND MAINTAINED ON SITE IN ACCORDANCE WITH TOWN ORDINANCE OR STANDARDS IN FORCE.
- 9. THE CONTRACTOR SHALL NOTIFY THE TREE WARDEN BEFORE REMOVING OR PRUNING ANY TREES THAT STAND ON TOWN OF LISBON PROPERTY.
- 10. ALL CURB/HANDICAP RAMP DESIGNS SHALL CONFORM TO ANSI, ADA, CT BASIC BUILDING CODE, TOWN OF LISBON STANDARDS IN FORCE AS DIRECTED THE THE TOWN BUILDING OFFICIAL.

SUGGESTED SEEDING MIXTURES AND PRACTICES

AREAS WHERE SEED MIX APPLIES	SEEDING MIXTURES BY WEIG	SHT	RATE PER 1,000 SQ. FT.	SEEDING DATES
ALL LAWN AREAS	RED FESCUES KENTUCKY BLUEGRASS PERENNIAL RYEGRASS	45% 45% 10%	1 LBS.	APRIL 1 – JUNE 15 OR AUG. 15 – OCT. 1
ROAD CUTS, FILLS, DIVERSION DITCHES, & STORMWATER BASINS	KENTUCKY TALL FESCUE REDTOP CREEPING RED FESCUE	47% 6% 47%	0.95 LBS.	APRIL 1 — JUNE 15 OR AUG. 15 — OCT. 1

WHERE TREES ARE TO BE RETAINED, THE SEED MIXTURE SHOULD BE ADAPTED FOR SHADY CONDITIONS.

TEMPORARY SEEDING	ANNUAL RYEGRASS OR PERENNIAL RYEGRASS	1-1/2 LBS.	WITHIN 7 DAYS AFTER SUSPENSION OF GRADING WORK

PERSON RESPONSIBLE FOR MAINTAINING
CONTROL MEASURES DURING CONSTRUCTION.

NAME

DAVID NOWAKOWSKI

ADDRESS

15 KENYON ROAD, LISBON, CT

TELEPHONE # (860)-376-1081

MAINTENANCE LOG

LOCATION	DESCRIPTION	DATE	INITIALS
PROJECT DATES		DATE	INITIALS

OJECT GROUNDBREAKING

FINAL STABILIZATION

33 Wilbur Cross Way, Mansfield, CT 06268 101 East River Drive, 1st Floor

PAVID NOWAKOWSKI

PMP

T5 KENYON ROAD
LISBON, CONNECTICUT

PMP

EROSION AND SEDIMENTATION

CONTROL NARRATIVE & NOTES

 ROJECT
 2019160
 NO.
 DATE
 DESCRIPTION
 BY

 OOK NO.
 192
 1
 02/10/2021
 HEALTH COMMENTS
 RAW

 ESIGNED
 KLD/PMP
 2
 04/02/2021
 CT DPH COMMENTS
 PM

 RAWN
 ZBC/RAC
 3
 06/15/2021
 CT DPH COMMENTS
 RA


 HECKED
 KLD
 4
 12/07/2021
 PZC COMMENTS
 PM


 OGO FILE
 2019160 ALL
 A
 12/07/2021
 PZC COMMENTS
 PM


DATE: 11/20/2020 SCALE: AS NOTED


PROJECT: #2019160


SHEET 11 OF 12












WETLAND IMPACT AREA DETAIL

TOTAL AREA 1084.82 S.F.



	LEGEND	
PROPERTY LINE		
ABUTTERS LINE		
EDGE OF PAVEMENT		
EDGE OF GRAVEL		
EXISTING CONTOUR		——————————————————————————————————————
STONE WALL		
RETAINING WALL		
LIMITS OF INLAND WETLA	ANDS	
FENCE		XXX
TREELINE		
PROPOSED CLEARING LIF	MIT	.~~~~~.
PROP UNDERGROUND W	ATER	w
PROP UNDERGROUND EL	LECTRIC	E
PROP UNDERGROUND CA	ABLE/TV	т
PROP UNDERGROUND FL	•	U
FLOOD ZONE LIIMIT		
100' UPLAND REVIEW LI	INE	
NOW OR FORMERLY		N/F
UTILITY POLE		
BOUNDARY POINT		©
IRON MONUMENT		•
STONE MONUMENT		•
TEST PIT		+
PERC HOLE		+

HEALTH COMMENTS PROJECT 2019160 NO. DATE DESCRIPTION B		0 C	JOB DATA		R E	REVISIONS	
BOOK NO. 192 1 02/10/2021 HEALTH COMMENTS 1 DESIGNED KLD/PMP 2 04/02/2021 CT DPH COMMENTS 2 04/02/2021 CT DPH COMMENTS 2 06/15/2021 CT DPH COMMENTS 2 CHECKED KLD 4 12/07/2021 PZC COMMENTS 2 COGO FILE 2019160 ALL 2 CHECKED COGO FILE 2 CHECKED COGO FILE 2 CHECKED COGO FILE COGO FILE	 DATE	PROJECT	2019160	ő	DATE	DESCRIPTION	B
L DESIGNED KLD/PMP 2 04/02/2021 CT DPH COMMENTS DRAWN ZBC/RAC 3 06/15/2021 CT DPH COMMENTS CHECKED KLD 4 12/07/2021 PZC COMMENTS COGO FILE 2019160 ALL 12/07/2021 PZC COMMENTS FILE 2019160 STP.dwg 12/07/2021 PZC COMMENTS	:	BOOK NO.	192	-	02/10/2021	HEALTH COMMENTS	RAC
DRAWN ZBC/RAC 3 06/15/2021 CT DPH COMMENTS CHECKED KLD 4 12/07/2021 PZC COMMENTS COGO FILE 2019160 ALL FILE 2019160 STP.dwg 3 06/15/2021 CT DPH COMMENTS FILE 2019160 STP.dwg	 11,	DESIGNED	KLD/PMP	2	04/02/2021	CT DPH COMMENTS	РМР
CHECKED KLD 4 12/07/2021 PZC COMMENTS COGO FILE 2019160 ALL FILE 2019160 STP.dwg 4 12/07/2021 PZC COMMENTS FILE 2019160 STP.dwg	/20	DRAWN	ZBC/RAC	3	06/15/2021	CT DPH COMMENTS	RAC
COGO FILE	 /20	СНЕСКЕD	KLD	4	12/07/2021	PZC COMMENTS	РМР
	020	COGO FILE	2019160 ALL				
		FILE	2019160 STP.dwg				

OWAKOWSKI

PROJECT: #2019160

SHEET 12 OF 12